

INTERNATIONAL
CONFERENCE ON
DESALINATION AND
SUSTAINABILITY

1 - 2 March 2012



الجمعية المغربية للمياه و تحلية المياه



in cooperation with



supported by



CASABLANCA 2012

MOROCCO

Jorf Lasfar: The Largest SWRO Desalination Plant in Morocco

Borja Martinez

MOR12-012



INDEX

1. Introduction
2. The Project
3. Design Conditions
4. Process & Plant Description
5. Design Highlights
6. Conclusions



1.- INTRODUCTION

OCP Group

- World's leading exporter of phosphate rock and derivative products

Contract

- Type of Contract LSTK
- EPC Contractor **CADAGUA** (Spain)

Project Milestones

- Start of the works June 2011
- Scheduled finish of the works September 2013



2.- THE PROJECT



OCP's Industrial Complex at Jorf Lasfar (120 km from Casablanca)





3.- DESIGN CONDITIONS

▪ WATER PRODUCTION

- Net Capacity
- | |
|---------------------------------------|
| 75,800 m ³ /d (Phase I) |
| 106,800 m ³ /d (Phase II) |
| 220,000 m ³ /d (Phase III) |

▪ SEAWATER CONDITIONS

- TSS
 - TDS
 - pH
 - Operating Temperature
- | |
|--------------------------------|
| 30 - 35 mg/l (spikes up to 40) |
| 37,000 mg/l |
| 8.0 |
| 13 – 23°C |




3.- DESIGN CONDITIONS

▪ PRODUCT WATER

- Use of Product Water Process & Drinking
- Chlorides < 200 mg/l
- Boron < 1 mg/l
- LSI +0.1 - +0.5
- Rest of parameters according to **NM 03.7.001 Anne 2006** standard on water quality for human consumption

4.- PROCESS & PLANT DESCRIPTION

■ PROCESS SCHEME



Intake


Pre-Treatment

RO & Post-Treatment



4.- PROCESS & PLANT DESCRIPTION

■ PLOT PLAN





4.- PROCESS & PLANT DESCRIPTION



▪ SEAWATER INTAKE

- | | |
|-------------------------|--|
| – Type of Intake | Open (existing cooling seawater channel) |
| – Screening System | |
| • Trash Racks | 4 x 33.3% / 30 mm |
| • Travelling Screens | 4 x 33.3% / 3 mm |
| – Seawater Intake Pumps | 3 x 50% (Phase I) |
- } Phase III



4.- PROCESS & PLANT DESCRIPTION

▪ SEAWATER INTAKE



Seawater Intake (3D-view)




4.- PROCESS & PLANT DESCRIPTION

▪ PRE-TREATMENT

– DAF System

- In service only during Harmful Algae Blooms and/or high level of hydrocarbons
- No. of lines 6 x 20%
- Coagulation Static mixer - FeCl_3
- Flocculation 2 stages - Coagulant Aid
- Flotation Cells equipped with sludge surface scrappers
- Recycling system

4.- PROCESS & PLANT DESCRIPTION



DAF Unit (typical cross section)



4.- PROCESS & PLANT DESCRIPTION

▪ PRE-TREATMENT

– UF System

- Required UF Permeate Quality

- TSS

Undetectable

- Turbidity

< 1 NTU (100% of time)

- SDI

< 2.5 (95% of time)

< 3 (100% of time)



4.- PROCESS & PLANT DESCRIPTION

▪ PRE-TREATMENT

– UF System (cont.)

- | | |
|-----------------------|---------------------------------|
| • Security Filtration | 4 x 33.3% self-cleaning filters |
| • No. of UF Racks | 20 x 5.5% |
| • Recovery | > 95% |
| • Design Flux (net) | < 75 l/mh |




4.- PROCESS & PLANT DESCRIPTION

▪ RO SYSTEM

– Permeate composition limiting parameters:

- $Cl < 200 \text{ mg/l}$
- $B < 1 \text{ mg/l}$

– 5 years AMLT




Double Pass Configuration
(2nd partial pass required from 17°C)



4.- PROCESS & PLANT DESCRIPTION

■ RO SYSTEM





4.- PROCESS & PLANT DESCRIPTION

▪ RO SYSTEM

– Cartridge Filters


- Security Filtration 8 x 14.3% (5 μ m)

– RO Trains

- 6 x 20% Production units (HPP + ERS + RO Racks 1st & 2nd pass) of 15,300 m³/d each
- 6 x 20% High Pressure Pumps
- 6 x 20% Energy Recovery Systems (pressure exchangers)

4.- PROCESS & PLANT DESCRIPTION

■ RO SYSTEM




RO Building (cross section)



4.- PROCESS & PLANT DESCRIPTION

■ RO SYSTEM

2nd Pass



Optimization of:

- Piping routes
- Footprint

1st & 2nd Pass RO Train



4.- PROCESS & PLANT DESCRIPTION

▪ POST-TREATMENT

– Remineralization

- CO₂ dosing
- Lime dosing

– Product Water Pumping Station

- 2 x 5,000 m³ Product Water Tanks
- 3 x 50% Product Water Pumps to OCP and ONEP reservoirs



5.- DESIGN HIGHLIGHTS

▪ FACING UP HARMFUL ALGAE BLOOMS (HAB's)

- HAB's have become a serious problem
- These events imply an increase of TSS and Organic Materia
- Conventional pre-treatments are not capable of facing up to this poor feed water quality
- Plant Availability is compromised
- DAF will reduce up to normal conditions the seawater quality



5.- DESIGN HIGHLIGHTS

▪ PLANT AVAILABILITY

- Continuous uninterrupted production of product water (100% availability)
- Stand-by units for main process systems as:
 - DAF
 - UF trains
 - RO trains for 1st & 2nd pass (HPP+ERD+RO racks)



6.- CONCLUSIONS

- Jorf Lasfar SWRO Plant is the largest plant up to date under construction in Morocco
- The treatment line, and in particular the advanced pre-treatment processes (DAF+UF), leads this plant to become the most advanced SWRO Plant using latest state-of-art in pre-treatments
- The use of highest design standards in combination to high grade materials selection will lead the installation to success for a long time



**THANK YOU VERY MUCH FOR YOUR
ATTENTION**



cadagua